

RFB: Red Barn Drainage Improvements

Project Location: 5401 Independence Rd. Weldon Spring, MO 63304

Bid Number: 261015

Pre-bid meeting: October 27, 2025 @ 10:00 am

Bid Due Date: November 3, 2025 @ 2:00 pm

Scope of Work

The City is requesting bids from qualified contractors for the installation of piped drainage underneath a sidewalk. The work shall include:

- Removal, or saw cuts, of sidewalk slabs, and proper disposal.
- Installation of new underground piping beneath the adjacent sidewalk that connects via "boot" to downspouts, and directs water to a suitable discharge point, such as a storm sewer or daylight.
- Restoration of disturbed surfaces, including concrete and landscaping.

Specifications

- Underground piping: [e.g., Schedule 40 PVC or SDR-35, minimum 4" diameter, with proper slope and cleanouts if required].
- All work must comply with local stormwater and building codes.
- Contractor is responsible for all permits, inspections, and utility locates.

Timeline

All work must be completed within 30 calendar days of Notice to Proceed.

Bid Submission Requirements

- Itemized cost of the proposal (materials, labor, site restoration, etc.) using the attached bid sheet.
- Proof of insurance and licensing.
- References for at least three similar projects completed in the last 3 years.

or

Bid should not be more than 3 (8.5x11) pages long, including the following bid sheet.

Addendum 1: All bids must be in a sealed envelope with "RFB: Red Barn Drainage Improvements" written in the lower right corner and delivered to

City of Weldon Spring
C.O. Albert Frasca
5401 Independence Rd.
Weldon Spring, MO 63304

City Contacts:

Albert Frasca (Primary) P: 636.441.2110 ext. 104 Mitchell Jordan

P: 636.441.2110 ext. 100

parks@weldonspring.org

communityrelations@weldonspring.org

RFB: Red Barn Drainage Improvements	provements			
Company Name:				
Contact Person:				
Contact Phone:				
Contact Email:				
Instructions – Fill in the unit cost and each item below. Please type, or write legibly	. Please type, or write legibly.			
ltem No.	Description of Work	Unit Cost (\$)	Total (\$)	Notes / Specifications
1	Mobilization, permits, utility locates			Include all required permits, inspections, and locates
2	Remove and dispose of the necessary existing sidewalk portions			Proper disposal per code
3	Excavate and install underground piping beneath si dewalk			Schedule 40 PVC or SDR-35, min 4" diameter
4	Connect drainage piping to discharge point			Includes fittings and restoration
5	Concrete/sidewalk restoration over piping trench			Match existing sidewalk thickness and finish
9	Site cleanup and restoration			Final grading, turf repair if needed
		Subtotal		
		Contingency (%)		
		Total Bid Amount		